

BOQ FOR CANDI BRANCH, INTERIOR FURNISHING WORK by SHOD

LOCATION -INDORE

SL	PARTICULARS	UNIT	QUANTITY	RATE	AMOUNT
A FLOORING					
1 VETRIFIED FLOORING					
A	Basic cost of tile. Tile Size- 4' x 4'. Providing and laying vitrified tile approved shade and removing the existing tile surface. The joints between the tiles is provided with 3mm thick. The joints between the tiles is provided with 3mm thick. Spacers and the joint filled with MK LATACRETE. EPOXY GROUT of approved shade. The rate should include providing and fixing necessary, protecting layer for the tile and any other items and charges to complete the work as per specification and direction of engineer in charge.	SFT	1150		
B	Specification same as above but for the ROBO ROOM using using 2' x 2' metallic finish ceramic tiles. With basic cost 225 / sft	SFT	80		
C	Basic cost of wooden flooring Rs.200.0/sft. Providing and fixing approved shade and make laminated wooden flooring 10mm thk with 6mm thk foam	SFT	237		
B PARTITIONS					
1 ENTRANCE GLASS SENSOR DOORS					
A	Providing and fixing 12mm thick toughened glass automatic sliding gate for the entrance using DORMA SENSOR fittings for the entrance , cost to be inclusive of fittings fittings, glass and necessary frosted film with approved design to be fixed on the glass . Providing and fixing of toughened glass automatic sliding gate for the entrance. (FITTING WILL BE PROCURED BY BANK)	SFT	171		
2 TOUGHNED GLASS PARTITION					
A	Providing and fixing 12mm thk toughened glass partition using enox/ ozone make patch fittings, includes necessary frosted films to be fixed on the glass, the joints between the glass to be filled with necessary silicone of approved make. Including all items and charges to complete the work as per specification.	SFT	674		
3 CABIN TOUGHNED GLASS DOORS					
A	Providing and fixing 12mm thk toughened glass door for cabins including enox/ ozone make patch fittings includes the bottom patch to be with automatic door closer ,a handle ,and a lock necessary frosted film to be fixed as per design on cabins Including all items and charges to complete the work as per specification.	SFT	45		
4 WOOD FRAMED FULL HT PARTITION					
A	Providing and fixing solid full ht wooden partition frame work made of frame work using 2.5"x 1.5"x 1.6mm thick alum hollow sections placed at 2' x2' , covered with 8mm MR GRADE commercial ply wood and exposed surfaces finished with 1mm thick glossy core laminate, the rate should include necessary hardware , cleaning etc., complete basic cost of laminate 100 /sft. Both side ply and laminate	SFT	570		

E		FALSE-CEILING											
A	Providing and finishing false ceiling as per design using 12mm thick plain gyp boards with all frame work using standard sections placed at 4' c/c in main direction and 2' c/c/ in cross direction , and the frame is mounted from the ceiling using anchor rods, the joint is finished with gyp powder with a tape.The ceiling is finished with 2 coats of putty and two coats of Emulsion paint , Including all items and charges to complete the work as per specification.	SFT	1500										
B	Providing and fixing false ceiling using 19mm thk ply as per design in the e lobby, bottom surface finished with 6mm thk marble finish solid surface LG make fixed with adhesive and polished Including all items and charges to complete the work as per specification.	SFT	150										
F		STORAGE											
A	Providing and fixing storage units using 19mm thk cut surfaces lipped with beech wood beadings 8mm thk ply backing with H8' x D1'6" x W3'. To be placed at the back end room of 24 x 7 section. All exposed surfaces laminated with approved shade cut surfaces lipped with beech wood beadings. The unexposed surfaces painted with approved enamel. paint , includes necessary hardware etc complete. Including all items and charges to complete the work as per specification.	NO	2										
G		MISCELLANEOUS											
A	Providing and fixing triangular elements in ceiling as per design made of using 19mm thk ply frame and mounted from the ceiling using anchor rods 12mm thk 3 nos per element The height of the unit is 6" and the bottom is fixed with 4mm thk acrylic sheet and the ends are covered with black stickers acrylic sheet . The inside of the box is designed to fix the LED tube lights and all inner surfaces painted with 2 coats of enamel. Including all items and charges to complete the work as per specification.	SFT	180										
B	Providing and fixing 12mm thk glass with ss brackets for set up box and other accessories.Size upto 2' x 1'. Including all items and charges to complete the work as per specification.	NO	4										
C	Providing and fixing roll up white backdrop attached to the ceiling for account opening machine. Preferably a semi-sized projector screen. Including all items and charges to complete the work as per specification.	NO	1										
D	Providing and fixing wall paper of approved shade and design. Including all items and charges to complete the work as per specification.	SFT	100										
E	Providing and fixing APPROVED SHADE ACP with alu frame at the entrance. Including all items and charges to complete the work as per specification.	SFT	250										
F	Providing and making new sandwich grill partition with the fixing of new 12mm square bar with 6 inch c/c and providing and making grill partition with framing and fixing new 12mm commercial ply from both sides with fixing new core laminate in proper line and level with necessary cleaning.	SFT	400										
H		DISMANTALLING											
A	Breaking the existing gypsum ceiling, partition and panelling and carting away the debris	SFT	2100										
B	Breaking and removing the existing 6" wall of the toilet and carting away the debris	SFT	150										
C	Breaking the existing flooring of the banking hall area and carting away the debris	SFT	2100										
D	Providing and making new P.C.C to the flooring with send cement in proper line and level	SFT	1700										
										TOTAL:	0		

Amount in Words, Rupees :

Date : Firm :

Tenderer Name :

Location:

SIGNATURE OF THE TENDERER WITH SEAL

APPROVED MAKES OF MATERIALS TO BE USED IN THE WORKS

1	19mm commercial plywood	MAKES: Century Ply, Green Ply, Anchor Board, Trojan, Frontier Ply, ASIS, ArchidPly, Kitply
2	12mm commercial plywood	MAKES: Century Ply, Green Ply, Anchor Board, Trojan, Frontier Ply, ASIS, ArchidPly, Kitply
3	8mm commercial plywood	MAKES: Century Ply, Green Ply, Anchor Board, Trojan Frontier Ply, ASIS, ArchidPly, Kitply
4	6mm commercial plywood	MAKES: Century Ply, Green Ply, Anchor Board, Trojan Frontier Ply, ASIS, ArchidPly, Kitply
5	Laminations	Formica, Greenlam, Sundek, Merino, Sunmica, Century, VIR
6	Prelaminated particle Board	Novopan, Duratuff, Bhutan ,kitlam
7	Glass	Triveni, Modi, Saint Gobain, ASAHI
8	Polish	Light house, Sheenlac, Melamine
9	Adhesive	Fevicol – commercial grade
10	Teakwood	Well seasoned Indian teakwood, minimum cost to be Rs 1800/- per cft
11	Hard wood	Well seasoned hardwood, Minimum cost shall be Rs 1200/- per Cft
12	Aluminium Sections	Jindal, Indal, Hindal
13	Locks	Godrej or EBCO
14	Paints	Asian, British, Duco
15	Cement Bonded Particle board	BISON
16	ACP	EURO bond / Aluco bond / Alstrong
17	Telescopic sliders	GODREJ
18	Flooring	Simpolo, EuroMAke
19	Solid Surface	Granium

Note: Any brands indicated under the items specifications in the schedule of quantities will prevail over the above indicated makes
Apart from the above makes, any further equivalent make as approved by the Bank, can also be used with prior permission from the Bank and Designer.