

**B.O.Q FOR INTERIOR WORK FOR CANARA BANK , CIRCLE OFFICE (GROUND FLOOR)
BHUBANESWAR.**

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
A	PARTITION WORK.				
1(A)	FULLY HEIGHT Partition (Semi Glazed) Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (conforming ISI 303) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eachingas per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects. (Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sft.	290.00		
2.0	LOW HEIGHT Partition (Semi Glazed) Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (confermin ISI 303) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eaching as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.	Sft.	180.00		
3.0	Pine wood beading Providing , fitting & fixing Pine wood beading in low height partition,cash counter front & low height cash counter front fasia with All pine wood beading surfaces to be finished in PU clear polish as directed . The work should be completed as per direction of architect including cost of all labour & material .				
	i)75mmx18 mm (as per design)	Rft	160.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
B	DOOR WORK.				
1.0	Doors – semi glazed				
	Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mmx 60mm, 28mm x80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition . The shutter will have part glazed 8mm thk float glass side beveled , high polished & part solid one covered with 9mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, handles (1'-0"long), aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	Sft.	70.00		
2.0	Door closer				
	Providing and fixing Godrej/ Doorset make over head door closers in door with necessary fixtures and fittings etc.	Nos	2.00		
3.0	Floor spring				
	Providing and fixing Godrej/ Door set make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		
C	FURNITURE WORK.				
1.0	Executive/ officer,s table				
	Providing and erecting in position, Manager's/Officer's Tables as per drawing and conforming to the following specifications.basic structure of 19 mm thick BWR grade block board for sides and modesty panel, finished with 1.00 mm thick laminate sheet of approved shade and make including inner faces.drawer-cum-cabinet uriit of approximate overall size of 400 x 500 x..600 inm (w x d x h) of 19 mm thick BWR grade block board and 12/6 mmthick BWR grade plywood. The drawer unit shall comprise of 3 sliding drawers: The drawer unit shall be finished with 1.00 mm thick laminate sheet of approved shade. Inner faces of cabinet shutters/drawers' shall be painted with 0.7 mm th inner mica The table top should be Modular 25mm th.MDF postform bull nose top .Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved quality. The item also include 8mm th. clear glass mechine cut and mechine polished over table top as per requirement .The job should be completed including all labour and material as per instruction of architect.				
	b) Approx. size of 5'-6" x 2'-6"X 2'-6"	Nos	1.00		
	c) Approx. size of 4'-6" x 2'-6"X 2'-6"	Nos	3.00		
	c) Approx. size of 4'-0" x 2'-6"X 2'-6"	Nos	12.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	Side storage cabinate				
	Providing and erecting in position side cabinet units of Modular 25mm th.MDF postform bull nose top of size 3'-6"x1'-6"x2'-6" and a front drawer unit consisting 2 Nos of drawer units slides on telescopic slider made up of 19mm th.ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7mm th. inner mica .Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs etc. of approved quality.	Sft.	150.00		
3.0	Storage Cabinate.				
	Providing and fixing of low height storage cabinate of Modular 25mm th.MDF postform bull nose top having 450mm. depth of made out of 19mm th. block board having one horizontal intermediate shalves. The storage unit should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shadea and the inner surface to be finished with 0.7mm th. inner mica .The work should be completed according to drawing and design including all labour and materials.Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs etc. of approved quality.	Sft	480.00		
4.0	Key board tray.				
	Providing and supplying metal Keyboard tray without Mousepad manufactured by M/s Godrej / EBCO . The keyboard is a pullout type, fixed to channels and screwed to below table top	Nos	16.00		
5.0	CPU Trolley.				
	Providing and supplying mobile metal CPU trolley manufactured by M/s Godrej / EBCO attached with 4 wheels for holding CPU and for its smooth movement	Nos	16.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
D	CELING WORK				
1.A	False ceiling (Gypsum board.)				
	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling shall be finished with painting 2 coats of plastic emulsion paint (velvet touch) of approved shade . Ceiling to be leveled & free from cracks including fixing GI perimeter	Sft.	680.00		
1.B	False ceiling (Gypsum board.- tray)				
	Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gypsum Co. Ltd. including finishing with White Plastic Emulsion Paint etc. as grove tray design to hold running light complete in all respects including all labour and material as per direction of engineer in charge .	Rft	190.00		
2.0	False celing (modular)				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile with sheihard gride Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	548.00		
E	OTHER WORK				
1(A)	Panelling (Mica finished)				
	P/f paneling without wooden framework but 12mm thick plywood fixed on leveled wall and finished with 1.00mm thk. laminate of approved make and shade , on all exposed surfaces on all exposed surfaces as per details and design	Sft.	200.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	Wall paper				
	Providing and fixing of wall paper of approve shade and pattarten of Marshall /Excell/ WK make to wall/partition as per instruction with adhesive including all labour and material . The work should be done as per instruction of architect.	Sft.	120.00		
3.0	Notice Board				
	Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. flot glass. The work should be done including all labour and material.	Sft	20.00		
4.0	Roller blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable roller blinds (Marvel make) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	180.00		
5.0	Wall Putty work.				
	Providing and applying wall puttyputty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	900.00		
6.0	Wall plastic paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hall including locker room, including preparation of surface, sand papering the intermediate coats, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	2,000.00		
7.0	Dismantling of brick work with plaster				
	Dismantling brick wall carefully by using chisel to cut & making good wall edges with 1:4 cement plaster including removal of debris from site.	Sft.	24.50		
8	RCC WORKS LINTLES				
	Constructing RCC Lintel of 10"x8" works in 1:1.5:3 mix (M20) concrete as per the requirement as directed by the Bank/ Architect. All RCC works should be machine mixed and vibrated, clear cover provided for reinforcement. The Rate shall include 4 No. of 12 # steel and 8# ring 6" c/c. The rate shall be inclusive of any scaffolding required, curing etc. Complete.	Rft	4.00		
9.0	PLASTERING OF WALLS				
	Providing & applying cement sand plaster of 1:4 proportion to existing brick / RCC walls & ceilings in single coat of avg. ¾" thk. Finished rough to receive plaster of paris levelling coat. The rate shall include necessary scaffolding, curing etc. Complete.	Sft.	50.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
10.0	M.S.COLLAPSIBLE GATE				
	Providing and Fixing MS Collapsible Gate double shutter made out of vertical double channels 12mmx8mm x 3mm at maximum 125 mm apart when fully stretched as specified, braced with flat iron diagonals 12 mm x 5 mm as specified in the item. The top and bottom rails shall be of M.S. section 25mm x 25mm x 6mm with 25 mm dia rollers in every fourth double channels.	Sft.	48.00		
	Where collapsible gate is to be fixed within the opening but is fixed along the outer surface of opening; the M.S. section at top shall be replaced by M.S. flat 40mm x 10mm. The necessary fittings such as bolts, nuts, locking arrangements, stoppers, handles, etc. shall be provided. The gates shall open and close smoothly and easily. T-iron rails shall be fixed to the lintel and floor with masonry nails embedded in cement concrete of lintel and floors at suitable spacing. The bottom runner shall be embedded with floor and proper groove formed and the floor shall be made good to match the rest of the flooring. At the sides, the end double channels shall be fixed with T-iron rails and also by holdfasts 200mm x 40mm x 4 mm bolted at one end to the end double channels and in the masonry in cement concrete 1:2:4 (nominal mix) blocks of size 115 mm x 75 mm x 230 mm, 3 nos. each side. The side masonry shall be made good to match the rest of the masonry finish. Two coats of antirusting paint to be provided to the gate.				
11.0	Façade of front entrance door.				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.It also contain the shutter and lock system for the collapsable gate to hide at the entrance as per instruction of the architect. The work should be completed in all respect including all labour and material.	Sft	98.00		
12.0	VINYL FLOORING				
	Supply & Fixing homogeneous & abrasion resistant Vinyl flooring 1.5 mm thick of desired shade & in desired patterns, in all cabins & corridors including cleaning of existing surface & using suitable adhesive to give smooth & even floor with all labour, material &T&P etc as required for proper completion of work . Rates shall include all taxes as applicable, nothing extra payable. Make- 1. WONDERFLOOR. 2. POLYFLOOR.	Sft	900.00		
TOTAL					

Total amount in words:-