

BOQ FOR INTERIOR WORK FOR CANARA BANK ,H.R.M. SECTION CIRCLE OFFICE BHUBANESWAR.

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
A	PARTITION WORK.				
2.0	LOW HEIGHT Partition (Semi Glazed)				
	Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (confermin ISI 303) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eaching as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.	Sft.	56.00		
3.0	Pine wood beading				
	Providing , fitting & fixing Pine wood beading in low height partition,cash counter front & low height cash counter front fasia with All pine wood beading surfaces to be finished in PU clear polish as directed . The work should be completed as per direction of architect including cost of all labour & material .				
	i)75mmx18 mm (as per design)	Rft	40.00		
B	DOOR WORK.				
1.0	Doors – semi glazed				
	Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mmx 60mm, 28mm x80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition . The shutter will have part glazed 8mm thk float glass side beveled , high polished & part solid one covered with 9mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, handles (1'-0"long), aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	Sft.	21.00		
2.0	Door closer				
	Providing and fixing Godrej/ Doorset make over head door closers in door with necessary fixtures and fittings etc.	Nos	1.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
C	FURNITURE WORK.				
1.0	Executive/ officer,s table Providing and erecting in position, Manager's/Officer's Tables as per drawing and conforming to the following specifications.basic structure of 19 mm thick BWR grade block board for sides and modesty panel, finished with 1.00 mm thick laminate sheet of approved shade and make including inner faces.drawer-cum-cabinet uriit of approximate overall size of 400 x 500 x..600 inm (w x d x h) of 19 mm thick BWR grade block board and 12/6 mmthick BWR grade plywood. The drawer unit shall comprise of 3 sliding drawers: The drawer unit shall be finished with 1.00 mm thick laminate sheet of approved shade. Inner faces of cabinet shutters/drawers' shall be painted with 0.7 mm th inner mica The table top should be Modular 25mm th.MDF postform bull nose top .Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire managers, foot rest etc. of approved quality. The item also include 8mm th. clear glass mechine cut and mechine polished over table top as per requirement .The job should be completed including all labour and material as per instruction of architect.				
	c) Approx. size of 4'-0" x 2'-6"X 2'-6"	Nos	7.00		
3.0	Storage Cabinate. Providing and fixing of low height storage cabinate having 450mm. depth of made out of 19mm th. block board having one horizontal intermidiate shalves. The storage unit should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shadea and the inner surface to be finished with 0.7mm th. inner mica .The work should be completed according to drawing and design including all labour and materials.Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs etc. of approved quality.	Sft	260.00		
4.0	Key board tray. Providing and supplying metal Keyboard tray without Mousepad manufactured by M/s Godrej / EBCO . The keyboard is a pullout type, fixed to channels and screwed to below table top	Nos	7.00		
5.0	CPU Trolly. Providing and supplying mobile metal CPU trolley manufactured by M/s Godrej / EBCO attached with 4 wheels for holding CPU and for its smooth movement	Nos	7.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
D	CELING WORK				
1.A	False ceiling (Gypsum board.)				
	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling shall be finished with painting 2 coats of plastic emulsion paint (velvet touch) of approved shade . Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all respects.	Sft.	150.00		
2.0	False ceiling (modular)				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile with sheihard gride Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	196.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
E	OTHER WORK				
1(A)	Panelling (Mica finished)				
	P/f paneling without wooden framework but 12mm thick plywood fixed on leveled wall and finished with 1.00mm thk. laminate of approved make and shade , on all exposed surfaces on all exposed surfaces as per details and design	Sft.	240.00		
4.0	Roller blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable roller blinds (Marvel make) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	80.00		
5.0	Wall Putty work.				
	Providing and applying wall puttyputty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	200.00		
6.0	Wall plastic paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hall including locker room, including preparation of surface, sand papering the intermediate coats, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	200.00		
9.0	PLASTERING OF WALLS/ CELING				
	Providing & applying cement sand plaster of 1:4 proportion with water proofing compound to existing brick / RCC walls & ceilings in single coat of avg. ¾" thk. Finished rough to receive plaster of paris levelling coat. The rate shall include necessary scaffolding, curing etc. Complete.	Sft.	300.00		
10.0	VINYL FLOORING				
	Supply & Fixing homogeneous & abrasion resistant Vinyl flooring 1.5 mm thick of desired shade & in desired patterns, in all cabins & corridors including cleaning of existing surface & using suitable adhesive to give smooth & even floor with all labour, material &T&P etc as required for proper completion of work . Rates shall include all taxes as applicable, nothing extra payable. Make- 1. WONDERFLOOR. 2. POLYFLOOR.	Sft	340.00		
11.0	DISMENTALLING				
	Removing and demolishing existing partition , counter, glass etc as per direction in phase manner to not affecting the working condition of the branch. Complete the job in all respect i.e clening, removing the deamaged material out side the premises as per instruction, including all labour.	L.S			
TOTAL					