

**BOQ OF INTERIOR FURNISHING WORK FOR CANARA BANK,
A.T.M AT KHUNTA KATA .**

Sl. No.	Particulars	Units	Qty.	Rate. (Rs)	Amount. (Rs)
1.0	Doors & glazed partition.				
	Providing and fixing Entrance Door (glazed) as per drawing in Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & side, glazed with 12 mm thick glass with SS H type SS handle of approved make with etching and frosting as per design. The fixed portion will be glazed with 8mm. th. glass. The item to include all necessary hardware of Stainless Steel finish as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion	Sft	24.50		
	b) Fixed portion	Sft	43.00		
2.0	Floor spring				
	Providing and fixing Godrej make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		
3.0	Wall panelling.				
	Providing and fixing in position Aluminium composite panel panelling with PVDF coating & LDPE core Altobond/Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.	Sft	250.00		
4.0	False ceiling				
	Providing & fixing at site plain Gypsum Board false ceiling made out of 12.5 mm thick paper reinforced gypsum board sheets to be fixed with main frame channels of size(80 mm x 26 mm x 0.5 mm) at every 450 mm c/c, intermediate channels of size(15 mm x 45 mm x 0.9 mm) at every 1220 mm c/c with perimeter channel 20 mm x 26 mm x 0.5 mm all along the wall shall be provided. The frame work to be suspended with strap bolts as recommended using rail plugs 12.5 mm dia x 35 mm long with 6 mm dia bolt and soffit cleat. Ceiling surface is to paint with two coats of distemper to get a smooth & even look including the cost of hard ware fittings, all labour & materials.	Sft	90.00		
5.0	Faceade cliding (ACP)				
	Providing and fixing in position aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond/Altobond/Alukbond Exterior grade 4mm thick including fabrication for the same with aluminium sections, required hard ware, silicon sealent (Dow coming 789), masking tape, necessary scaffolding etc. It also include the trap door shutter with magnetic catch. The work should be completed including all labour and material.	Sft	70.00		
TOTAL					

SL.N	DESCRIPTION OF ITEMS	AMOUNT (Rs)
1.0	BRANCH INTERIOR FURNISHING WORK	
2.0	ATM INTERIOR FURNISHING WORK	
TOTAL		