

**BOQ OF INTERIOR FURNISHING WORK FOR CANARA BANK,
A.T.M AT DASAPALLA BRANCH .**

Sl. No.	Particulars	Units	Qty.	Rate.	Amount
1.0	PARTITION				
	Providing , fitting & fixing 75mm thick double skined partition work made out of 1"x1.5" aluminium section frame work. The sections are to be placed 600mm c/c. 6 mm ACP to be nailed over the both surface of the frame work and 1mm thick laminate of approved shade to be pasted over the exposed surface and inner surface is to be painted with two coats of enamel paint over one coat of primer , including cost of all labour & material .(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sft	60.00		
2.0	Doors & glazed partition.				
	Providing and fixing Entrance Door (glazed) as per drawing in Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & side , glazed with 12 mm thick glass with SS H type SS handle of approved make with etching and frosting as per design. The fixed portion will be glazed with 8mm. th. glass . The item to include all necessary hardware of Stainless Steel finish as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion	Sft	24.00		
	b) Fixed portion	Sft	24.00		
3.0	Floor spring				
	Providing and fixing Godrej make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		
4.0	Wall panelling.				
	Providing and fixing in position Aluminium composite panel panelling with PVDF coating & LDPE core Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow coming 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.	Sft	160.00		
5.0	False celing				
	Providing & fixing at site plain Gypsum Board false ceiling made out of 12.5 mm thick paper reinforced gypsum board sheets to be fixed with main frame channels of size(80 mm x 26 mm x 0.5 mm) at every 450 mm c/c, intermediate channels of size(15 mm x 45 mm x 0.9 mm) at every 1220 mm c/c with perimeter channel 20 mm x 26 mm x 0.5 mm all along the wall shall be provided . The frame work to be suspended with strap bolts as recommended using rail plugs 12.5 mm dia x 35 mm long with 6 mm dia bolt and soffit cleat. Ceiling surface is to paint with two coats of distemper to get a smooth & even look including the cost of hard ware fittings,all labour & materials	Sft	50.00		
5.0	Mineral Fiber Board/Grid Celing:				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.).	sft	36.00		

6	Faceade cliding (ACP)				
	Providing and fixing in position almunium composit panel boxing with PVDF coating & LDPE core laminated Eurobond/Altobond/Alukbond Exterior grade 4mm thick including fabrication for the same with almunium sections, required hard ware, silicon sealent (Dow coming 789), masking tape, necessary scaffolding etc. It also include the trap door shutter with magnetic catch. The work should be completed including all labour and material.	Sft	70.00		
7	WRITING LEDGE				
	Providing and fixing writing ledge as per design made out 19mm block board with necessary groove patterns ,1.0mm laminate to be cladded. 18mm thk.approved colour granite with half round moulding at facia to be provided on top of the writing ledge.A divider made of 19mm thk.block board to be provided. Whit beach/ White ceader lipping with natural polish to be used in all exposed areas. Inside of writing ledge to be enamel painted.The work to be completed in all respect.	NO	1.00		
8	CHEQUE DEPOSIT BOX				
	Providing and fixing cheque deposit box made out of 19mm thk block board & finished with 1.0mm thk. Laminate & inside to be synthetic enamel painted.a 1" high slit & small door with key and locking arrangement to be done for dropping & taking out the slips.The work to be completed as per the design,direction & approval of the architect.	Each	1.00		
9	WALL PAINTING WITH PUTTY				
	Providing and painting two coats of synthetic plastic emultion paint of approved shade and colour over one coat of primer with all cost of materials and labour.	Sft	120.00		
TOTAL					

SL.NO.	DESCRIPTION	AMOUNT (Rs)
1	BRANCH INTERIOR FURNISHING WORK	
2	ATM INTERIOR FURNISHING WORK	
	TOTAL	