

**Amendment-1 to the Tender dated 31/01/2019 for “Modular furnishing works at New Circle office building, Rail Nilayam, Secunderabad”.**

It is decided to amend the following in respect of the above RFP:

Sl. No.	Page No.	Clause No./ Item no.	Existing	Amended
1	120	1	Modular work Station L shape: Size : 1500 (L) X 600 (D) X 1200 (H):Providing and fixing modular 60mm type work station L-Shape with 60mm thickness main spine and return spine considered , gable ends below ,table top 25mm thick post -formed MDF wood, post formed, with cable grommet provision, and above table top with 60mm aluminum partitions fabric board considered on main spine and return spine with fabric and Below table top with 60mm partitions with 9mm MDF wood on main spine and return spine considered , gable ends considered in 25mm MDF Board, On main spine 1 No's of race way, considered below table top bottom level considered for the provision of electrical, data level and 1 No skirting level for wire management etc. as suitable making complete as per the design. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.	Modular work Station L shape: Size : 1500 (L) X 600 (D) X 1200 (H):Providing and fixing modular 60mm type work station L-Shape with 60mm thickness main spine and return spine considered , gable ends below ,table top 25mm thick post -formed MDF wood, post formed, with cable grommet provision, and above table top with 60mm aluminum partitions with pin board tile and white board tile considered on main spine and return spine. and Below table top with 60mm partitions with 9mm MDF Board interior grade on main spine and return spine considered , gable ends considered in 25mm MDF Board interior grade, On main spine 1 No's of race way, considered below table top bottom level considered for the provision of electrical, data level and 1 No skirting lvl for wire management etc. as suitable making complete as per the design. The rate shall be inclusive of all the material , labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.
2	120	2	Modular work Station STRAIGHT shape: Size : 1200 (L) X 600 (D) X 1200 (H):Providing and fixing modular 60mm type work station L-Shape with 60mm thickness main spine and return spine considered , gable ends below table top 25mm thick post -formed MDF board / BWR plywood/pre laminated Particle	Modular work Station STRAIGHT shape: Size : 1200 (L) X 600 (D) X 1200 (H):Providing and fixing modular 60mm type work station L-Shape with 60mm thickness main spine and return spine considered , gable ends below table top 25mm thick post -formed MDF board / BWR plywood/pre laminated Particle

			board post formed , with cable grommet provision and above table top with 60mm aluminum partitions fabric board considered on main spine return spine with fabric and Below table top with 60mm partitions with 9mm PLB board main spine and return spine considered , gable ends considered in 25mm PLB Board. On main spine 1 No's of race way is considered below table top bottom level considered for the provision of electrical, data level and 1 No skirting level for wire management etc. as suitable making complete as per the design. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.	board post formed , with cable grommet provision and above table top with 60mm aluminum partitions with pin board tile and white board tile considered on main spine and return spine and Below table top with 60mm partitions with 9mm MDF board interior grade main spine and return spine considered , gable ends considered in 25mm MDF Board interior grade. On main spine 1 No's of race way is considered below table top bottom level considered for the provision of electrical, data level and 1 No skirting level for wire management etc. as suitable making complete as per the design. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.
3	120	3	Supplying, Providing and fixing modular mobile pedestal for storage of size 400LX450DX640H finished with 18mm pre laminated board plb with suitable lock and key and castors as per the design etc. as suitable making complete as per the design. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.	Supplying ,Providing and fixing modular mobile pedestal for storage of size 400LX450DX640H finished with 18mm MDF Board interior grade with suitable lock and key and castors as per the design etc. as suitable making complete as per the design. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.

All the other Instructions and Terms & Conditions of the above Tender remain unchanged. Please take note of the above Amendment while submitting your response to the subject Tender.

Date: 16/02/2019  
Place: Hyderabad

Deputy General Manager