

CANARA BANK, HOWRAH STATION ATM
SUMMARY FOR INTERIOR FURNISHING & ELECTRICAL WORKS

SUMMARY OF ESTIMATED AMOUNT

1	FURNISHING WORK	= Rs.	-
2	ELECTRICAL WORK	= Rs.	-
TOTAL		= Rs.	-

GST EXTRA



CANARA BANK, HOWRAH STATION ATM
B O Q FOR INTERIOR FURNISHING WORKS

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	Providing , fabricating and erecting lay in type tegular or drop type Modular False Ceiling (ARMSTRONG make) of 600 x 600 mm. grid with approved brand of armstrong. The rate shall include the additional cost of Tee and L supports and other accessories near the ends/ odd size edges/corners. Provide additional length support from the ceiling to the false ceiling grid wherever necessary, making necessary openings for electrical light fittings, alarm detectors and any other fixtures. No extra payment for making openings in the panel/grids for the purpose of light fittings. Item rate shall include all the taxes, transportation, erection, loading and unloading and any other incidental expenditure for completing the work.	50.00	sq. ft.		
2	Providing & Fixing fully glazed 12 mm. clear Toughened Glass Door (in one shutter) with floor mounted pivotted door spring hinges to shutters fitted with patch fittings & floors with plate & screws including cutting holes & mending good with cement mortar, with sticker design bank's name, logo, bands etc. (polished edge as directed) fitted with 30 mm. dia. 100 mm. X 500 mm. long stainless pair of 'C' handles (both inside & outside) with all accessories, floor spring complete as per design & direction.	55	sq. ft.		
3	Providing & fixing ACP wall panelling with 3mm thick (0.5mm + 2 mm + 0.5mm) ACP in approved colours all complete with approved aluminium sub structure, aluminium brackets, silicon sealants, gaskets, PVDF coating in approved colour etc. all complete including bird/ vermin proof closer at the bottom and flashing at top, complete as per instructions & drawings.	200.00	s.ft.		
4	Providing and fixing Low height Cabinet(7ft.x3ftx2ft) made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finished and 4" skirting throughout. Division of shutters shall be made equally according to the length of the storage. A 19 mm thk. Fixed BWR Ply shelf on battens shall be provided at 16" intervals from the base. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. Cost of all fitting like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all complete. As per drawing and instruction.	21.00	s.ft.		
5	Opening of rolling shutter and refixing the sanme after greasing,painting,oiling alla complete	1.00	L.S.		
GRAND TOTAL					



CANARA BANK, HOWRAH STATION ATM					
B O Q FOR ELECTRICAL WORKS					
SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1a	Providing and laying 1.1. KV grade 4 x 10.0 sq. mm. & 2 x 6 sq. mm. PVC coated copper conductors in PVC conduits from Main Panel to lighting & power DBs. Including all necessary terminals etc. complete.	15.00	r. m.		
1b	Providing & fixing 1.1. KV grade 4 x 6 sq. mm. & 2 x 2.5 sq. mm. PVC coated Coper Conductor in PVC conduit for UPS supply from panel to UPS, including all accessories, terminals etc. complete.	30.00	r. m.		
1c	Providing & fixing 1.1. KV grade 2 x 4 sq.mm. & 1 x 1.5 sq.mm. pvc insulated multi stranded copper wire in suitable size pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories. (for A.C. & glow sign board wiring)	20.00	r. m.		
1d	Providing and fixing 1.1. KV grade 2 x 2.5 sq mm. & 1 x 1.5 sq. mm. Copper conductor for UPS DB To ATM/PUM etc.. The item includes all necessary accessories such as Saddles cable glands etc. complete.	30.00	r. m.		
4	Providing & fixing POINT WIRING for Ceiling and wall lights / fan. The item includes Circuit wiring from DB to the switch board with 2 x 2.5 Sq. mm. PVC insulated copper conductor with 1.5 sq. MM PVC insulated copper conductor for earthing in appropriate size of PVC conduits ISI mark , point wiring to be laid with 2 x 1.5 Sq. mm. PVC insulated copper conductor with all necessary accessories, such as saddles etc. on surface or embedded in wall, chasing the walls and making the surface neat afterwards. The item includes switch 6 AMP MK/ CRABTREE with (Double module) all base plates & cover plates, M.S. box of same make etc. 3 - plate ceiling rose to be provided for Exhaust fans complete. Each switch board should have at least 1 no. 5 Amp raw power socket.				
a	Providing and fixing point wiring with same pecifications as MAIN point wiring above : one point to be controlled by one switch.	5.00	unit		
6	Removing & refixing existing all electrical fixtures like DB, switch board etc	1.00	L.S		
b	Providing and fixing Copper Earth Wire 8 guage in pvc conduit in Floor / walls From pipe earthing to Main Panel Board Complete.	30.00	r.m		
	GRAND TOTAL				-

