

BOQ OF INTERIOR WORK FOR CANARA BANK AT KHUNTA KATA BRANCH

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
A	PARTITION WORK.				
1	FULLY HEIGHT Partition (Semi Glazed)				
(A)	Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section and/or as per frame work shown in the drawings with 6 mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with etching and frosting as per design and fitted with SS finished patch panel and 2"x2" T.W. member for door sides and glass sides and T.W. door frame to take 12 mm thick glass with etching and frosting.All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sft.	320.00		
2.0	LOW HT. HEIGHT Partition (Semi Glazed)				
	Providing and fixing in position partly glazed 4'-6" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section and/or as per frame work shown in the drawings with 6 mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with etching and frosting as per design and fitted with SS finished patch panel and 2"x2" T.W. member for door sides and glass sides and T.W. door frame to take 12 mm thick glass with etching and frosting.All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.	Sft.	80.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
3.0	Full glazed Partition				
	Providing , fitting & fixing 12mm thick float glass partition with chemically eaching as per design.the partiton will be supported with S.S patch panel fittings as per drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as per direction of architect including cost of all labour & material .	Sft.	45.00		
4.0	Teek wood beading				
	Providing , fitting & fixing teek wood beading in low height partition,cash counter front & low height cash counter front fasia with All teak wood beading surfaces to be finished in melamine polish of matching laminate colour as directed . The work should be completed as per direction of architect including cost of all labour & material .				
	i)75mmx12mm (as per design)	Rft	70.00		
	ii)38mmx19mm (as per design)	Rft	25.00		
B	DOOR WORK.				
1.0	Doors – semi glazed				
	Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mmx 60mm, 28mm x80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition . The shutter will have part glazed 8mm thk float glass side beveled , high polished with body itching of st globain & part solid one covered with 6mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary WB wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, handles, Godrej make night latch, hydraulic door Closure, aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	Sft.	98.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
2.0	Doors – glazed				
	Providing and fixing twin,- stile door made of 50, mm thick well seasoned teak wood of special design for top and bottom stiles, fixed, portion with 8mm thick clear float glass and open able portion with 12mm thick etching glass with bank logo frosted design with necessary sand blasting/granular blasting to be provided and edge should be machine beveled polished glass, necessary hardware fixtures of approved make and design, viz. double action floor spring, brass flush bolt. Stain finish stainless steel decorative handle (approx. 300mm long) on both faces, complete as per drawing and instructions. Wooden surfaces shall, be polished in approved shade N.C. lacquer in mat satin finish. The work to be completed as per design and specification of all complete				
	a) Open able portion	Sft	24.50		
	a) Fixed portion	Sft	11.00		
3.0	Wicket gate (up to 1.5M. ht)				
	Specification same as 2A , but fully solid	Sft.	12.00		
4.0	Door closer				
	Providing and fixing Godrej make over head door closers in door with necessary fixtures and fittings etc.	Nos	4.00		
5.0	Floor spring				
	Providing and fixing Godrej make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		
6.0	Night latch lock				
	Providing and fixing Knightlatch lock of Godrej make to cash counter door with necessary fixture and fittings etc as per direction of architect.	Nos	1.00		
C	FURNITURE WORK.				
1.0	Front officer counter.				
	Providing and fixing of counter table top of 5'-0"X2'-9" and one side drawer unit of 1'3"x3'-0"x2'-6" size consisting 2 Nos of drawer units slides on telescopic slider and one cupboard unit with locking arrangement made up of 19mm th.ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate . and cable manager are to be fixed as per drawing and design.It also include one 12"x12" edge polished 12mm th. glass panel vertically fixed with SS stude with coloured eatched bank logo as per design and drawing. The work is to be completed with all labour and material including all the hardware required.	Nos	3.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
2.0	Cash Counter				
	Providing and fixing of counter table top of 2'-9" wide and front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th.ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate . and cable manager are to be fixed as per drawing and design.It also include a 12mm th. fully blue coloured eached and edge polished 15" wide horizontal glass member fixed with the partition by SS patchpanel and a vertical 12mm th fully eached glass member from table top to horizontal glass member fixed with SS patchpanel. It also include one 12"x12" edge polished 12mm th. glass panel vertically fixed with SS stude with coloured eached bank logo as per design and drawing. The work is to be completed with all labour and material including all the hardware required.	Nos	1.00		
3.0	Manager's table				
	Providing modular executive type manager table top of size 6'0"x3'-0"x2'-6", a side credenza of size 3'-6"x1'-6"x2'-6" and a front drawer unit consisting 3 Nos of drawer units slides oon telescopic slider made up of 19mm th.ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate . The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. It also include 8mm clear glass table top with edge polished .The work should be completed including all labour and material.	Nos	1.00		
4.0	Officer's table				
	Providing modular executive type manager table top of size 4'6"x2'-6"x2'-6", a side credenza of size 3'-0"x1'-6"x2'-6" and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th.ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate . The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. It also include 8mm clear glass table top with edge polished .The work should be completed including all labour and material.	Nos	1.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
5.0	Storage Cabinate.				
	Providing and fixing of low height storage cabinate having 450mm. depth of made out of 19mm th. block board .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shadea and the inner surface is finished with 0.7 mm th inner laminate. surfaces are to be finished with as per design The work should be completed according to drawing and design including all labour and materials.	Sft	50.00		
6.0	Side storage cabinate				
	Providing and erecting in position side / back cabinet units with sliding shutters of approx. size of 400 mm deep x 700 mm high made of 19mm thick BWR grade block boards including intermediate shelves as per drawing linstructions Exposed block board surfaces shall be finished with 1.00 mm laminate sheet of approved shade and make . Inner faces to be finished with 0.7mm th. mica .Free edges of block board shall have polished steam beech/teak wood half round moulds (out of 20 x :20 mm sections.) Quoted rates shall include cost of necessary hardware, viz. handles, locks with keys in duplicate.,' etc (Actual face area will be rneasured for payment purpose)	Sft.	40.00		
7.0	Key board tray.				
	Providing and supplying metal Keyboard tray without Mousepad manufactured by M/s Godrej / EBCO . The keyboard is a pullout type, fixed to channels and screwed to below table top	Nos	6.00		
8.0	CPU Trolley.				
	Providing and supplying mobile metal CPU trolley manufactured by M/s Godrej / EBCO attached with 4 wheels for holding CPU and for its smooth movement	Nos	6.00		
D	OTHER WORK				
1.0	Panelling				
	Encasing to columns , banking hall entrance where ever shown in drawings by fixing 6mm ply to the frames made out of 40mm x20mm. 2 nd class treated hard wood like Kasi/Giringa by means of nailing or screwing over with 1 mm tk laminate fixed by means of adhesive having grooves & necessary white beach beading as directed by the Architect finished with melamine finished WB wood moulding & cornice lining . At places niches shall be created to accommodate 12 mm tk soft board & fabric of approved quality fixed with necessary frame work of wood . Nitches shall be leaped with WB wood which is also melamine polished. The O H planter box as specified in other items at certain height projected from the column / walls / partitions etc fixed as per Architect's drawing/ direction. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft.	200.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
2.0	Suggestion box				
	Supplying and erecting free-standing suggestions box of overall size , 450 mm long x 300 mm deep x450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete. with hardware. fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with 0.7 mm th inner laminate of approved shads and quality .	Nos	1.00		
3.0	Cheque drop box				
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with 0.7 mm th inner laminate.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.designand quality.	Nos	1.00		
4.0	Writing platform for customers & application form set	Rft	3.00		
	Providing , fitting , fixing writing plat form at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mm tk on top & hard wood beading ducco painted . At least 10 nos vertical slip in chalan shelves attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6" height , 6" wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of consultant .				
5.0	Notice Board				
	Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. flot glass. The work should be done including all labour and material.	Sft	10.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
6.0	Wall plastic paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hall including locker room, including preparation of surface, sand papering the intermediate coats, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	3,500.00		
7.0	Wall Putty work.				
	Providing and applying wall puttyputty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	1,100.00		
8.0	False ceiling (Gypsum board.)				
	False Ceiling (Gypsum Board)Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gupsm Co. Ltd. including trap doors for A.C. Unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1” x 1” for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft.	440.00		
8-B	False ceiling (Gypsum board.- tray)				
	Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gupsm Co. Ltd. including finishing with White Plastic Emulsion Paint etc. as grove tray design to hold running light complete in all respects including all labour and material as per direction of engineer in charge .	Rft	70.00		
9.0	False ceiling (Armstrong)				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1” x 1” for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	388.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
10.0	Façade of front entrance door.				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.	Sft	60.00		
11.0	Glazed display board.				
	Providing and fixing glazed display board as per design and instruction of architect of size 1'6"x2'-6" of 12mm th. Glass of edge polished and 1" edge beveled and fixed on wall with 1" SS stude as per direction . The work include all labour and materials.	Nos.	4.00		
12.0	M.S grill door .				
	Providing and fixing M.S grill foldable door door made up of 12mm sq. bar with 5" C/C spacing as per direction of architect. The door should be provisioned for double lock system. The cost also include for two coat of enammel paint over one coat of red oxide primer for grill and dismantalling the existing collapsable gate.. The work should be completed including all labour and materials.	Sft	32.00		
13.0	Electrical panel board cover				
	Providing and fixing of electrical panel board cover made up of 19mm ply with two shutter at the front having T.W luvvers as per drawing and design, it allso have furnished with locking arrangement. The exposed surface is finished with 1mm. Th. Laminates and inner surface is finished with two cote of plastic emulsion paint over one coate of primer . The work should be completed including all hardware, material and labour.	Sft	28.00		
14.0	Vertical blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable vertical blinds (Marvel or its equivalent, as approved) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	120.00		
TOTAL					