

**BOQ FOR INTERIOR & FURNISHING AT CANARA BANK BRANCH AT MALLANWALA KHAS.**

S.No.	Item	Quantity	Units	Rate	Amount
<b>PART-1 :INTERIOR WORKS</b>					
<b>1</b>	<b>FALSE CEILING (MINERAL FIBRE GRID TILE): ARMSTRONG Prima Dune / Sand Supreme, RH 99 &amp; micro log edge with black lining</b>				
	Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules.	520.00	sft		
	Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				
<b>2</b>	<b>GYPSUM BOARD FALSE CEILING WITH STEPS:</b>				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypboard over a grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20mmx27mmx30mmx0.5mm)	480.00	sft		
	,supported securly, fixed round the perimeter to receive end of the ceiling section (MF5) and the outer edges of gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm ) at 1200mm c/c in the one direction and the ceiling section (MF5 of dimensions 80mm x 26mm x 0.5mm at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.The gypsum board sheets are screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete including 2-3 coats of oil bound distamper, ove a coat of primer,as per instructions of Architect or Engineer				
<b>3</b>	<b>WOODEN PARTITION INCLUDING DOOR (FULL HEIGHT / 7'-0" HIGH)</b>				
	Providing & fixing partly glazed full height partition <b>made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically &amp; horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw.</b> The frame work to be clad with <b>8mm thick commercial ply</b> and 1.0mm thick laminate as per pattern on both sides, with 6mm thick clear float glass fixed with teak wood beading as/ drawing, finished in spirit polish.				
	All wood to be treated with wood preservatives of approved ISI quality, complete in all respect as/ instructions of Architect/ Engineer in charge.				
<b>a)</b>	<b>CASH CABIN PARTITIONS (7'-0" HIGH)</b>	90.00	sft		
<b>b)</b>	<b>PARTITION upto CEILING Ht.</b>	90.00	sft		
<b>4</b>	<b>WOODEN PARTITION INCLUDING FLAP DOOR (LOW HEIGHT)</b>				

	Providing & fixing partition 4'-6" high (overall) made of <b>44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically &amp; horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw.</b> The frame work to be clad with <b>8mm thick ply</b> and 1.0mm thick laminate as per pattern on both sides upto 2'-9" height. 12 mm thick glass 1'-6" high(overall) having curved top, with etching fixed with stainless steel glass holders/brackets at bottom and side with top surface and other side free. Teak wood beading shall be provided at all exposed edges of partition, which shall be finished in spiri tpolish. All wood to be treated with wood preservatives of approved ISI quality. All the edges of 12mm glass shall be duly grinded & polished.	270.00	sft		
<b>5a</b>	<b>MAIN ENTRANCE DOOR OF 8MM THICK GLASS ALUMINIUM SECTION AT TOP &amp; BOTTOM (WITH LOGO/ETCHING FILM):</b>	56.00	sft		
	Providing and fixing main entrance doors as per drawing made of 8 mm thick clear plain float glass ,fixed in powder coated aluminium glass door section (SP-2607 of HINDALCO or equivalent)				
	size: 87x38.8x3.2mm, with rubber gasket at top & bottom, 12" long stainless steel handle of Italica / Golden/equivalent make on both sides. The door will be mounted on double action, heavy duty floor spring of ISI make and locks , the cost of which will be included in the rate. The vertical visible edges of glass shall be grinded & polished. Bank's Logo & etching pattern shall be affixed on glass in 3M etching film as per drawing.				
<b>5b</b>	<b>MAIN ENTRANCE GLAZING OF 8MM THICK GLASS ALUMINIUM SECTION AT TOP &amp; BOTTOM (WITH LOGO/ETCHING FILM):</b>	92.00	sft		
	Providing and fixing main entrance glazing as per drawing made of 8 mm thick clear plain float glass ,fixed in powder coated aluminium glass door section (SP-2607 of HINDALCO or equivalent)				
	size: 87x38.8x3.2mm, with rubber gasket at top & bottom.The vertical visible edges of glass if any shall be grinded & polished. Etching pattern shall be affixed on glass in 3M etching film as per drawing.				
<b>6</b>	<b>WALL PANELLING</b>				
	Providing and Fixing of wall panelling with 1.0mm thick laminate fixed over <b>8 mm thick commercial ply including grooves as / pattern given. The 8 mm ply shall be fixed to a wooden frame made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically &amp; horizontally.</b> The outer edges of the panelling shall be provided with teak wood lipping with melamine polish, complete as/instrucions of Architect/Engineer in charge.	0.00	sft		
<b>7</b>	<b>WOODEN SHUTTER BOXING FOR ROLLING SHUTTER</b>				
	Providing and fixing of wooden boxing using 19mm thick <b>commercial ply</b> all around with 1.0mm thick laminate over it as per pattern given. All the exposed edges of board shall be provided with teak wood lipping, complete as per satisfaction of Architect/Engineer in charge.	0.00	sft		
<b>8</b>	<b>WOODEN BOXING FOR ELECTRICAL PANEL</b>				
	Providing & fixing at site cabinet 7' height having overall depth of 1'-6". The cabinet & shutters shall be made of <b>19mm thick commercial ply</b> with 1.0mm thick laminate on outer surfaces. All the edges of board shall be provided with teak wood lipping. The shutters shall be mounted on Piano hinges and provided with magnetic catchers, Lock and towerbolt as required. Louvered panels shall be provided in the shutters as per drawing, for ventilation of hot air. All internal surfaces and wooden lipping shall be provided with spirit polish, complete in all respects.	90.00	sft		
<b>9</b>	<b>HARDWARE</b>				
<b>a)</b>	Providing and fixing of Night latch Lock Godrej make in aluminium/ wooden doors, complete in all respects.	3.00	no.		
<b>b)</b>	providing and fixing mortice locks with handle in doors as approved, complete in all respects.	6.00	no.		
<b>c)</b>	providing and fixing hydraulic door closer Hyper/ Everrite/ Godrej ISI marked make, to doors complete in all respects.	6.00	no.		
<b>d)</b>	providing and fixing double action floor spring for main door Hyper/ Everrite/ Godrej ISI marked make, complete in all respects.	2.00	no.		

<b>10</b>	<b>TABLES &amp; COUNTERS</b>				
	Providing and placing table made of <b>19mm thick commercial ply</b> and 1.0mm thick laminate. The front of the table top shall be projected as per drawing. Provision for 3" dia. Round / square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. Teak wood lipping will be provided on all the edegs of the table and the drawers. The table shall have a laminated keyboard tray of size 600x450 fixed on channels, as per manufacturer's instructions / specifications. One drawer & cupboard below shall be provided on One Side of the Table. <b>Non visible surfaces i.e. inside leg space of table, inside drawers shall be finished with 0.8mm thk white/off white laminate of approved make.</b>				
	All exposed teak wood edegs / teak wood lipping / beading shall have spirit polished. The Table shall also include foot rest , as per drawing , complete in all respects.				
a)	BM Table: Size 6'-0"x3'-0"x2'-6"	1.00	no.		
b)	Officer Table: Size 5'-0"x2'-6"x2'-6"	1.00	no.		
c)	Clerical Table: Size 5'-0"x2'-6"x2'-6"	5.00	no.		
d)	P/ F a Help Desk Table having a size of 4' X 1'-9" X 2'-6" ht. in <b>19 mm thk.commercial ply</b> for top & sides. Apron in 12 mm thk commerial ply, and 3" pencil drawers etc finished in 1 mm thk laminate of approved make shade as per the design/ drawing etc complete.	1.00	no.		
<b>11</b>	<b>CASH COUNTER</b>				
e)	providing & fixing 2 level Cash Counter with granite top at 3'-9" made out of <b>19mm thick commercial ply</b> and 1.0mm thick laminate of approved shade. Provision for 3" dia. Round / square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. Teak wood lipping will be provided on all the edegs of the table and the drawers. The table shall have a laminated keyboard tray of size 600x450 fixed on channels, as per manufacturer's instructions / specifications. Three drawers shall be provided on One Side of the Table,with the top drawer having partitions for sorting currency notes. <b>All drawers to be provided with autolock in cash counter.</b>	5.00	rft		
	<b>Non visible surfaces i.e. inside leg space of table, inside drawers shall be finshd with 0.8 mm thk. white/off white laminate of approved make.</b> All exposed teak wood edegs / teak wood lipping / beading shall have <b>spirit</b> polished. The Table shall also include foot rest , as per drawing , complete in all respects.				
<b>12</b>	<b>SIDE CREDENZA FOR OFFICERS:</b>				
	Providing & Fixing Side credenza 2'-3" high, 3'-0" long & 18" deep as per drawings, having 2 sets of two filing drawers of 18" width (placed vertically) and One open compartment with shelf, made of <b>19 mm thick commercial ply</b> & 1.0mm thick laminate on all visible surfaces including open shelves. The drawers shall be made of 12mm thick (sides & back), 6mm thick plywood(bottom) & <b>19mm thick comm ply</b> (front fascia with laminate), with teak wood lipping on all edges, running on telescopic drawer channels . <b>Non visible surfaces i.e. inside leg space of table, inside drawers shall be finshd with 0.8 mm thk. white/off white laminate of approved make.</b> All the edges of beading / lipping shall be provided with <b>spirit</b> polish, complete in all respects.	2.00	no.		
<b>13</b>	<b>LOW HEIGHT STORAGE CABINETS (2'-6" HIGH)</b>				
	Providing & Fixing storage cabinets 2'-6" high & 18" deep as per drawings, having 2 sets of two filing drawers / Shutters as per drawings, made of <b>19 mm thick commercial ply</b> & 1.0mm thick laminate on all visible surfaces including open shelves. The drawers shall be made of 12mm thick (sides & back), 6mm thick plywood(bottom) & <b>19mm thick comm ply</b> (front fascia with laminate), with teak wood lipping on all edges, running on telescopic drawer channels . <b>Non visible surfaces i.e. inside leg space of table, inside drawers shall be finshd with 0.8 mm thk. white/off white laminate of approved make.</b> All the edges of beading / lipping shall be provided with <b>spirit</b> polish, complete in all respects.	27.50	rft.		

<b>14</b>	<b>FULL HEIGHT STORAGE CABINETS (8'-0" HIGH)</b>				
	Providing & Fixing storage cabinets 8'-0" high & 18" deep as per drawings, having Shutters as per drawings, made of <b>19 mm thick commercial ply</b> & 1.0mm thick laminate on all visible surfaces including open shelves. The drawers shall be made of 12mm thick (sides & back), 6mm thick plywood(bottom) & <b>19mm thick comm ply</b> (front fascia with laminate), with teak wood lipping on all edges, running on telescopic drawer channels . <b>Nor visible surfaces i.e. inside leg space of table, inside drawers shall be finshd with 0.8 mm thk. white/off white laminate of approved make.</b> All the edges of beading / lipping shall be provided with <b>spirit</b> polish, complete in all respects.	0.00	rft.		
<b>15</b>	<b>12 MM GLASS (IN FRONT OF COUNTERS/ CASH CABIN FRONT) :</b>				
	Providing and fixing 12 mm thick, clear plain float glass of approved pattern fixed in vertical position 6" above counter level as per drawing, fixed on both sides on wooden partitions with superior quality stainless steel glass holders (2 no. on both sides). A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. Only glass area with maximum height shall be measured for the purpose of pavment	65.00	sft.		
<b>16</b>	<b>WALL MOUNTED VOUCHER TRAY:</b>				
	Providing & Fixing Customer Voucher tray of overall size 4'-0" x 1'-6" x 1'-6", fixed to wall with brackets, at 39" height from floor level, having compartments for vouchers as per drawings, with space for writing on top at 39" level. Outer frame made of <b>19mm thick commercial ply</b> with 1.0mm laminate on all outer visible surfaces with teak wood lipping on all edges of board and shall be spirit polish. The compartments shall be made of 8mm thick glass, fixed with stainless steel glass holders of EBCO make. All the edges of glass shall be duly grinded & polished.	1.00	no.		
<b>17</b>	<b>TEXTURE PAINT</b>				
	Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.	0.00	Sq.ft		
<b>18</b>	<b>PLASTIC EMULSION PAINT</b>				
	Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more coats of plstic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Architect/Engineer-In-Charge).Make:- Asian paints/ICI Dulux/Nerolac.	0.00	Sq.ft		
	TOTAL				